


NOTES:

1. TIME AND DURATION OF SHUTDOWN SHALL BE DETERMINED BY THE SUPERINTENDENT OF THE MARYSVILLE DIVISION OF WATER.
2. THE CONTRACTOR SHALL NOTIFY ALL WATER CONSUMERS EFFECTED BY THE PROPOSED WORK AT LEAST 24 HOURS PRIOR TO THE SHUTDOWN.
3. ALL BENDS SHALL BE SECURED BY MEGA-LUGS AND RODDING OR OTHER METHODS AS APPROVED BY THE WATER SUPERINTENDENT. CONCRETE SHALL THEN BE PROVIDED IN ACCORDANCE WITH THE CITY OF MARYSVILLE STANDARD DETAILS AND SPECIFICATIONS FOR OVER BENDS AND SAG BENDS.
4. THE RELOCATED LINES SHALL BE LAID TO THE NEW LINE AND GRADE, TESTED AND DISINFECTED PRIOR TO SHUT DOWN OF EXISTING MAIN AND CONNECTION OF THE RELOCATED LINES TO THE EXISTING MAIN. IF LINES TO BE RELOCATED ARE PRIVATE, THEY WILL TEST AND BACTERIA TEST COMPLETE LINE.
5. ALL WATER LINES SHALL BE DISINFECTED BY SWABBING WITH A 5% HYPOCHLORITE SOLUTION IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF A.W.W.A. C-601.
6. MATERIALS USED IN LOWERING SHALL MATCH MATERIALS OF ADJACENT WATERLINE.

NOT TO SCALE

DATE: MARCH 2023	STANDARD CONSTRUCTION DRAWING	
	<p>WATERLINE LOWERING</p>	<p>DRAWING NO. WTR-06</p>