



**NOTES**

1. TIME AND DURATION OF SHUT DOWN SHALL BE DETERMINED BY THE SUPERINTENDENT, DIVISION OF WATER.
2. THE CONTRACTOR SHALL NOTIFY ALL WATER CUSTOMERS EFFECTED BY THE PROPOSED WORK AT LEAST 24 HOURS IN ADVANCE OF SHUT DOWN.
3. ALL BENDS SHALL BE SECURED BY MEGA-LUGS AND RODDING OR OTHER METHODS AS APPROVED BY THE SUPERINTENDENT OF WATER. CONCRETE SHALL THEN BE PROVIDED IN ACCORDANCE WITH THE CITY OF MARYSVILLE STANDARD DETAILS AND SPECIFICATIONS FOR OVER BENDS AND SAG BENDS.
4. THE RELOCATED LINES SHALL BE LAID TO THE NEW LINE AND GRADE, TESTED AND DISINFECTED PRIOR TO SHUT DOWN OF EXISTING MAIN AND CONNECTION OF THE RELOCATED LINES TO THE EXISTING MAIN. IF LINES TO BE RELOCATED ARE PRIVATE, THEY WILL TEST AND BACTERIA TEST COMPLETE LINE.
5. ALL WATER LINES SHALL BE DISINFECTED BY SWABBING WITH A 5 PER CENT HYPOCHLORITE SOLUTION IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF A.W.W.A. C-801

Date: 3/02/2018

Standard Construction Drawing



Typical Water Line  
Lowering Detail

Drawing No.  
WTR-22